

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-20123-00-00
Spot: S2NESE Sec/Twnshp/Rge: 9-18S-14W
1650 feet from S Section Line, 660 feet from E Section Line
Lease Name: KEENER Well #: 2-D
County: BARTON Total Vertical Depth: 3430 feet

Operator License No.: 32012
Op Name: MADDOX, JOHN DBA MAD DOG OIL C
Address: 862 NW 70TH AVE
OLMITZ, KS 67564

PROD Size: 5.5 feet: 3428 w/75 sxs cmt
SURF Size: 8.625 feet: 282 w/200 sxs cmt

#111 48

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 02/24/2004 9:00 AM
Plug Co. License No.: 7023 Plug Co. Name: KLIMA WELL SERVICE, INC.
Proposal Rcvd. from: JOHN MADDOX Company: MAD DOG OIL COMPANY Phone: (316) 653-4563

Proposed
Plugging
Method:

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 02/24/2004 2:15 PM KCC Agent: CASE MORRIS

Actual Plugging Report:

Perfs:

Packer was stuck in the hole at 1600'. Shot off packer at 1580'.
Pumped 25 sxs 60/40 pozmix - 10% gel cement down backside.
Blew out casing. Cement coming up outside of cellar.
Pumped 125 sxs cement down tubing.
Pulled to 800' and circulated with 60 sxs cement.
POOH.
Tied onto casing and pumped 165 sxs cement with 150# hulls.
Max. P.S.I. 300#. S.I.P. 150#.

RECEIVED
MAR 05 2004
KCC WICHITA

Remarks: ACID SERVICES, INC.

Plugged through: CSG

District: 04

MM

Signed _____

Case Morris

(TECHNICIAN)

INVOICED

DATE 3-15-04

INV. NO. 2004061283

MAR 03 2004

CLINTON OIL COMPANY #2-D KEENER 100' N, S/2 NE SE 9-18-14W

Contr. GARVEY DRIG Cty. BARTON

Geol. Pool BOYD

E. 1947 KB Cm. 10/19/67 Cp. 11/23/67 IP P 35 BOPD, NW

API 15-009-20,123

ARB 3428-30
GRAV 36.70

SMP Tops	Depth	Datum	Csg. 8" 282/200 SX, 5" 3428/75
ANHY	995	+1042	DST 3192-3212/1', 5' M, BHP 37-
B/ANHY	935	+1012	34#, FP 27-32#
TOP	2878	- 931	
SH MARKER	2916	- 969	DST 3326-46/1', 5' MD, BHP 0-0#
LS MARKER	2994	-1047	FP 0-0#
QH SH	3029	-1082	
HEFB	3117	-1170	DST 3396-3430/1', 120' MO, BHP
TOR	3130	-1183	1031-987#/30", FP 68-102#
DOUG	3142	-1195	
BRIM	3189	-1242	FU 375' OIL, NW/12 HRS, A 26, BLD
LANS	3197	-1250	3.73 BOPH/2 HRS, 200' OB, FU 1400'
BKC	3402	-1455	OIL, N2/42 HRS, BLD 2.73 BOPH,
ARR	3427	-1480	200' OB, POP
RTD	3430	-1483	

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS