

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-155-21470-00-00
Spot: NENENW Sec/Twnshp/Rge: 35-22S-9W
330 feet from N Section Line, 2310 feet from W Section Line
Lease Name: SIEGFRIED Well #: 1-35
County: RENO Total Vertical Depth: 3700 feet

Operator License No.: 31160

SURF Size: 8.625 feet: 293

Op Name: PHILLIPS EXPLORATION COMPANY L.

\$120²⁵

Address: 4109 IRONWOOD
WICHITA, KS 67226

Well Type: OIL

UIC Docket No:

Date/Time to Plug: 02/10/2004 11:45 AM

Plug Co. License No.: 5929

Plug Co. Name: DUKE DRILLING CO., INC.

Proposal Rcvd. from: STEVE STEVENS

Company: DUKE DRILLING CO., INC.

Phone: (316) 267-1331

Proposed Plugging Method: Fill hole with heavy mud and spot cement through drill pipe. Spot 35 sxs. cement at 1,300', spot 35 sxs. cement at 800', spot 35 sxs. cement at 350', and spot 25 sxs. cement at 60'. Fill rathole with 15 sxs. cement. Fill mousehole with 10 sxs. cement.

Plugging Proposal Received By: VIRGIL CLOTHIER

Witness Type: NONE

RECEIVED
KANSAS CORPORATION COMMISSION

Date/Time Plugging Completed: 02/10/2004 2:00 PM

KCC Agent: MICHAEL WILSON

MAR 8 2004

Actual Plugging Report:

Perfs:

CONSERVATION DIVISION
WICHITA, KS

Filled hole with heavy mud and spotted cement through drill pipe. Spotted 35 sxs. cement at 1,300', spotted 35 sxs. cement at 800', spotted 35 sxs. cement at 350', and spotted 25 sxs. cement at 60'. Filled rathole with 15 sxs. cement. Filled mousehole with 10 sxs. cement.

RECEIVED
KCC DISTRICT #2

MAR 3 2004

WICHITA, KS

Remarks: USED 60/40 POSMIX W/4% GEL BY ALLIED CEMENTING CO., INC. INVOICE #14391

Plugged through: DP

District: 02

Signed

Michael Wilson

(TECHNICIAN)

INVOICED

DATE

3-15-04

NO. NO.

2004061284