

DISTRICT CONSERVATION AGENT'S REPORT

*B*

TO:

State Corporation Commission  
Conservation Division  
800 Bitting Building  
Wichita, Kansas

15-147-00103-00-00

FILE NO. \_\_\_\_\_

LOCATION CW $\frac{1}{2}$  SW NE

SEC. 33 TWP. 1 RGE. 18 *w*

Dry Hole \_\_\_\_\_ Abandoned Oil Well x Abandoned Gas Well \_\_\_\_\_

I have today completed supervision of plugging of:

Well No. A-1 Lease Ann Lowe *Box 69W*

Operator Smitherman & Cohen Address El Dorado, Kans

Field \_\_\_\_\_ County Phillips

Total Depth 3571 Feet.

(Describe briefly the manner in which the well was plugged)

8 5/8" at 245' circulated with cement - 5 1/2" at 3561' with 125  
sax cement behind.

Filled with chat to 3550', set 4 sax cement with dump bailer,  
pulled 1500' 5 1/2", filled with mud to 245', set rock and 10 sax  
cement, mud to 35', set rock and 10 sax cement to bottom cellar.

RECEIVED

STATE CORPORATION COMMISSION

JUL 31 1952

CONSERVATION DIVISION

Wichita, Kansas

*Leon Kelly*  
District Conservation Agent

Date 7-28-52

**PLUGGING**  
FILE SEC. 33 T. 1 R. 18  
BOOK PAGE 34 LINE 7

*F*