

KANSAS



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
JUN 25 1971  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

15-147-00432-00-00

Operator's Full Name Sierra Petroleum Company, Incorporated,

Complete Address Box #232, Russell, Kansas.

Lease Name Jackson Well No. 1

Location CW/2--NW-SW Sec. 33 Twp. 1 Rge. (E) (W)18

County Phillips Total Depth 3838'

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D & A

Other well as hereafter indicated \_\_\_\_\_

Plugging Contractor Southwest Casing Pulling Company, Incorporated,

Address Box #364, Great Bend, Kansas. License No. 399

Operation Completed: Hour 2:00 PM Day 22 Month 6 Year 1971

The above well was plugged as follows:

242'--8 5/8" Surface casing, cement circulated with 175 Sx.  
3726'--5 1/2" Production casing cemented on bottom with 175 Sx. Well plugged back to  
3691'. Top perforations from 3467' to 3469'.

Pushed plug to 3400', sanded back to 3375' and set 5Sx. cement with dump bailer.

Pulled 5 1/2" casing (1280') and squeezed well initially with 5 sacks hulls and 15 sacks  
gel and followed with 150 Sx. cement from 1200' to 700' then 11 sacks gel from 700'

to 260' and followed with 25 Sx. cement from 260' to 185' then 4 sacks gel from 185'

to 30' and finally 10 Sx. cement from 30' to bottom of cellar. Maximum pump-in press-  
ure--300#. Final shut-in pressure--150#. Mudding and cementing by Allied Cementing  
Inc.,).

I hereby certify that the above well was plugged as herein stated.

Signed: W. L. Nichols  
Well Plugging Supervisor

INVOICED

DATE 6/25/71

INV. NO. 3913-W