

15-147-00757-00-00
DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. NE 80
LOCATION NW SE SW
SEC. 33 TWP. 1 RGE. 18

Dry Hole _____ Abandoned Oil Well Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 3 Lease Jackson
Operator L. B. Lawrence Address Box 414 Great Bend, Kans
Field _____ County Phillips
Total Depth 3580 Feet.

(Describe briefly the manner in which the well was plugged)

8 5/8" at 268' circulated with cement - 5 1/2" at 3580'
with 125 sax cement behind - perforated at 3494'
Filled with sand to 3480', set 4 sax cement with dump bailer,
pulled 1100' 5 1/2", filled with mud to 268', set rock and 15 sax
cement, mud to 35', set rock and 10 sax cement to bottom cellar.

RECEIVED
STATE CORPORATION COMMISSION

JAN 24 1953

CONSERVATION DIVISION
Wichita, Kansas

[Signature]
District Conservation Agent

Date 1-21-53

PLUGGING
FILE SEC 33 T 1 R 18
BOOK PAGE 75 LINE 17