

15-147-00758-00-00
DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. _____

LOCATION NW SW SW

SEC. 33 TWP. 1 RGE. 18 W

Dry Hole _____ Abandoned Oil Well Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 2 Lease Jackson

Operator L. B. Lawrence Address Box 414 Great Bend, Kans

Field _____ County Phillips

Total Depth 3544 Feet.

(Describe briefly the manner in which the well was plugged)

8 5/8" at 187' circulated with cement - 5 1/2" at 3544' with
125 sax cement behind .

Filled with sand to 3525', set 4 sax cement with dump bailer,
pulled 1100' 5 1/2", filled with mud to 187', set rack and
15 sax cement, mud to 55', set rack and 10 sax cement to
bottom cellar

PLUGGING
FILE SEC 33 T 1 R 18 W
BOOK PAGE 23 LINE 45

RECEIVED
STATE CORPORATION COMMISSION
JAN 20 1953
CONSERVATION DIVISION
Wichita, Kansas

District Conservation Agent
Date 1-14-53