

15-147-00985-00-00
DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. _____

LOCATION NW NW SW

SEC. 33 TWP. 1 RGE. 18 W

Dry Hole _____ Abandoned Oil Well Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 1 Lease Jackson

Operator L. B. Lawrence Address Box 414 Great Bend, Kans

Field _____ County Phillips

Total Depth 3542 Feet.

(Describe briefly the manner in which the well was plugged)

8 5/8" at 180' circulated with cement - 5 1/2" at 3542' with 125 sax
cement behind - perforations at 3522'.

Filled with sand to 3510', set 4 sax cement with dump bailer,
pulled 2200' 5 1/2", filled with mud to 180', set rock and 15 sax cement,
mud to 35', set rock and 10 sax cement to bottom cellar.

RECEIVED
STATE CORPORATION COMMISSION
JAN 20 1953
CONSERVATION DIVISION
Wichita, Kansas

District Conservation Agent
Date 1-18-53

PLUGGING
FILE SEC 33 T 1 R 18 W
BOOK PAGE 74 LINE 1