

KANSAS

Form CP-3
Rev. 6-26-62

59

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

RECEIVED
AUG 21 1967
CONSERVATION DIVISION
WICHITA, KANSAS

15-147-01011-00-00

Operator's Full Name T. W. Jackson Oil Co.

Complete Address: R. R. # 4 Phillipsburg, Kansas

Lease Name Jackson Well No. 1

Location NW NE Sec. 33 Twp. 1 Rge. 18 (E) (W) X

County Phillips Total Depth 3695

Abandoned Oil Well X Gas Well _____ Input Well _____ SWD Well _____ D & A _____

Other well as hereafter indicated: _____

Plugging Contractor: Southwest Casing Pulling

Address: Box 364 Great Bend, Kansas License No. 399

Operation Completed: Hour 1 P Day 18 Month 8 Year 1967

The Above well was plugged as follows:

Total Depth 3695' 8 5/8 csg set at 206' cwc 130 sc.

4 1/2 csg set at 3694' cw 100 sc cement.

Perf. 3505-06

Filled with sand to 3490' and dumped 4 sc cement with dump Bailer.

Recov. 1460' of 4 1/2 csg.

Squeezed 8 5/8 csg with 35 sc gel and 115 sc cement.

Mud(1460'-900') cement (600'-900') mud (50'-600') cement (0-50')

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Geo. T. Massey
Well Plugging Supervisor

DATE 8-21-67

INV. NO. 6168-W