

DISTRICT CONSERVATION AGENT'S REPORT

R

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

15-147-19049-00-00

FILE NO. _____

LOCATION NW NW SE

SEC. 33 TWP. 1 RGE. 18 *W*

Dry Hole _____ Abandoned Oil Well X Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 2 Lease Ann Lowe

Operator Smitherman & Cohen Address El Dorado, Kans

Field _____ County Phillips

Total Depth 3570 Feet.

(Describe briefly the manner in which the well was plugged)

10 3/4" at 193' circulated with cement - 7" at 3569' with
175 sax cement behind - Lane Wells plugs to 3504' - top perf
at 3491'.

Filled with chat to 3480', set 5 sax cement with dump bailer,
pulled 1300' 7", filled hole with mud to 193', set rock
and 15 sax cement, mud to 35', set rock and 10 sax cement to
bottom cellar.

Edward Kelly
District Conservation Agent

Date 8-2-52

PLUGGING RECEIVED
STATE CORPORATION COMMISSION
AUG 11 1952
CONSERVATION DIVISION
Wichita, Kansas
FILE SEC 33 T 1 R 18
BOOK PAGE 37 LINE 5