

DISTRICT CONSERVATION AGENT'S REPORT

[Handwritten signature]
15-147-19050-00-00

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. _____

LOCATION NW NW SE

SEC. 33 TWP. 1 RGE. 18

lost hole

Dry Hole _____ Abandoned Oil Well _____ Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 2 Lease Ann Lowe

Operator Honaker Drilling Co Address 1818 Broadway
Great Bend, Kans

Field _____ County Phillips

Total Depth 3570 Feet.

(Describe briefly the manner in which the well was plugged)

10 3/4" at 206' circulated with cement.

Well was completed as to T. D. Company was running 7" casing.

Casing stuck at 2660', lost 300' of 7" at 2660'.

Pumped hole full rotary mud, set wood plug at 190', followed by

15 sax cement, heavy mud to 40', set wood plug, 1/2 sack hulls

and 10 sax cement to bottom cellar.

RECEIVED
STATE CORPORATION COMMISSION
MAR - 7 1951

CONSERVATION DIVISION
Wichita, Kansas

[Handwritten signature]
District Conservation Agent

Date 3-6-51

PLUGGING
FILE SEC 33 T 1 R 18
PAGE 66 LINE 7