

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-167-20748-00-00
Spot: NWNWNW Sec/Twnshp/Rge: 10-13S-14W
4950 feet from S Section Line, 4950 feet from E Section Line
Lease Name: SCHMIDT Well #: 1
County: RUSSELL Total Vertical Depth: 3130 feet

Operator License No.: 101
Op Name: KCC FEE FUND PLUG
Address: 130 S. MARKET
WICHITA, KS 67202

PROD Size: 4.5 feet: 3129 w/135 sxs cmt
SURF Size: 8.625 feet: 200

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 02/25/2004 10:00 AM
Plug Co. License No.: 3152 Plug Co. Name: POE SERVICING INC
Proposal Rcvd. from: ED POE Company: POE SERVICING INC. Phone: (785) 475-3422

Proposed
Plugging
Method:

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 02/25/2004 2:00 PM KCC Agent: CASE MORRIS

Actual Plugging Report:

Perforated at 700' and 1375'.
Pressured backside to 500#.
Ran tubing to 1400'.
Pumped 40 sxs 60/40 pozmix - 10% gel cement with 200# hulls.
Pulled to 700' and circulated with 80 sxs cement and 200# hulls.
POOH.
Tied onto casing and pumped 30 sxs cement.
Max. P.S.I. 800#. S.I.P. 400#.

RECEIVED
MAR 05 2004
KCC WICHITA

Perfs:

Top	Bot	Thru	Comments
700	1375		

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: CSG

District: 04

Signed *Case Morris*
(TECHNICIAN)

MAR 03 2004

BARTON OIL CO.

#1 SCHMIDT

10-13-14W
NW NW NW

504 E. 5TH, RUSSELL, KS.; 2
CONTR EMPHASIS OIL OPERATIONS

CTY RUSSELL

GEOL R. P. NIXON

FIELD MACHIN EXT

E 1639 RB CB/31/75 CAPO ISSUED 8/28/75 IP P 30 BOPD + 70 BWPD

LANS 2851-3001 OA

API 15-167-20,748

+	+	+
+	+	+
+	+	+

SMP	TOPS	DEPTH	DATUM
GR HAY		2190	- 551
DVR LS		2216	- 577
2ND TARK		2225	- 586
TARK LS		2262	- 623
TOP		2530	- 891
HEEB		2756	-1117
TOR		2775	-1136
LKC		2808	-1169
PKC		3067	-1428
ARB		3112	-1473
RTD		3130	-1491

8-5/8" 200, 4 1/2" 3129/135SX
NO LOG
DST (1) 2810-30/30-30-30-30, REC 25'
DM, SIP 89-38#, FP 32-32#
DST (2) 2826-2865/30-30-30-30, REC 385'
O SP M, SIP 712-663#, FP 142-209#
DST (3) 2885-2930/60", REC 165' OCM +
FO, 45' OILY WTR, SIP 873-857#/30",
FP 57-154#
DST (4) 2952-3010/60", REC 90' GIP, 95'
OCM, SIP 726-446#, FP 57-98#
MICT - PF 2998-3001, A 1000, PF 2898-
2902, A 1000, PF 2851-2855, A 1000, REC:
LD, POP

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS