

State of Kansas



ROBERT B. DOCKING Governor  
 DALE E. SAFFELS Chairman  
 JULES V. DOTY Commissioner  
 JAMES O. GREENLEAF Commissioner  
 RAYMOND B. HARVEY Secretary  
 JACK GLAVES Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg.

212 N. Market

WICHITA, KANSAS 67202

15-147-20065-06-00

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
 STATE CORPORATION COMMISSION  
 MAR 21 1969  
 CONSERVATION DIVISION  
 Wichita, Kansas

J. Lewis Brock  
 Administrator  
 500 Insurance Building  
 Wichita, Kansas 67202

Dear Sir:

Mr. Fickle of Red Tiger Drlg. has this

date requested permission to plug the following described well:

Mr. Fickle guarantees payment of the plugging fee.

Operator's full Name: Don H. Peaker Et al

Complete Address: P. O. Box 1595 Pueblo, Colo.

Lease Name: Goddard Well No. 1

Location: NE NE SW Sec. 29 Twp. 1 Rge. 18 (E)(W) X

County: Phillips Total Depth 365 Oil Well

Gas Well  Input Well  SWD Well  D & A XX Lost Hole

Mr. Fickle was instructed to plug the well as follows:

Gun pits, circulate heavy mud, set cementing plug at 1100' and displace

70 sk cmt thru drill pipe. Heavy mud to 210' set cementing plug and

displace 20 sk cmt thru drill pipe. Heavy mud to 40' set cementing

plug, 1/2 sk hulls and 10 sk cmt to base of cellar. Plug rat hole with

2 sk cmt.

Very truly yours,

Geo F. Massey  
 Conservation Division Agent