



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

15-147-00432-00-00

RECEIVED
STATE CORPORATION COMMISSION
JUN 25 1971
CONSERVATION DIVISION
Wichita, Kansas

Dear Sir:

Mr. Albert Unruh of Southwest Casing Pulling Co. has this date requested permission to plug the following described well:

Mr. Unruh guarantees payment of the plugging fee.

Operator's full Name: Sierra Petroleum Company,

Complete Address: Box #232, Russell, Kansas.

Lease Name: Jackson Well No. 1

Location: CW/2-NW-SW Sec. 33 Twp. 1 Rge. (E)(W) 18

County: Phillips Total Depth 3830' Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Unruh was instructed to plug the well as follows:

242'--8 5/8" Surface casing, cement circulated with 175 Sx.
3726'--5 1/2" Production casing cemented on bottom with 175 Sx. Well
plugged back to 3691'. Top perforations from 3467' to 3469'.

Push plug to 3400', sand well back to 3375 and set 5 Sx. cement with
dump bailer. Pull 5 1/2" casing and squeeze well with 5 sacks hulls, 30
sacks gel and 190 Sx. cement, staged.

Very truly yours,

W. L. Nichols
Conservation Division Agent