



Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT RECEIVED

STATE CORPORATION COMMISSION

OCT 4 1974

CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

15-147-20042-00-00

Operator's Full Name Leland R. Baird

Complete Address Logan, Kansas 67646

Lease Name Kent "G" Well No. 2

Location NE NW NE Sec. 22 Twp. 1 Rge. (E) (W) 18

County Phillips Total Depth 3552'

Abandoned Oil Well XX Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Southwest Casing Pulling

Address Box 364 Great Bend, Kansas License No. 399

Operation Completed: Hour 10:- A Day 2 Month 10 Year 1974

The above well was plugged as follows:

- Total Depth 3552' 8 5/8 csg set at 211' cwc 150 sk.
- 4 1/2 csg set at 3550' cw 200 sk cem.
- 4 1/2 csg PBDT 3418' top perf. (3345-3352)
- Filled 4 1/2 csg W/sd (3418-3325) dumped 4 sk cem W/dump bailer. (3325-3295)
- Cutoff & recovered 2750' of 4 1/2 csg.
- Pumped down 8 5/8 csg with 17 sk gel & water W/400 lbs hulls -70 sk 50-50 poz 6% -
- 13 sk gel & water -released 8 5/8 plug & pumped 50 sk 50-50 poz 6% by Allied.

I hereby certify that the above well was plugged as herein stated.

Signed: Lee F. Massey
Well Plugging Supervisor

INVOICED

DATE 10/4/74
NO. 40-W