

DISTRICT CONSERVATION AGENT'S REPORT

*R*

TO: 15-147-30184-00-00

State Corporation Commission  
Conservation Division  
800 Bitting Building  
Wichita, Kansas

FILE NO. \_\_\_\_\_  
LOCATION NE ~~NE~~ SE  
SEC. 22 TWP. 1 RGE. 18

Dry Hole \_\_\_\_\_ Abandoned Oil Well \_\_\_\_\_  Abandoned Gas Well \_\_\_\_\_

I have today completed supervision of plugging of:

Well No. 1 Lease ~~camp~~ Kent  
Operator Lawrence & Meltzer Oil Address Box 414  
Great Bend, Kans  
Field \_\_\_\_\_ County Phillips  
Total Depth 3505 Feet.

(Describe briefly the manner in which the well was plugged)

8 5/8" at 178' circulated with cement. 5 1/2" at 3504' with 175 sax  
cement behind - Perforations at ~~3425'~~ 3432'.

Filled with chat to 3425', set 4 sax cement with dump bailer,  
pulled 2250' 5 1/2", filled hole with mud to 175', set rock bridge  
and 15 sax cement, filled with mud to 35', set rock and 10 sax  
cement to bottom cellar.

RECEIVED  
STATE CORPORATION COMMISSION

OCT 27 1951

CONSERVATION DIVISION  
Wichita, Kansas

*Debra J. Perry*  
District Conservation Agent

Date 10-26-51

FLUGGING  
FILE SEC 22 1 R18W  
BOOK PAGE 120 LINE 5