

KANSAS



STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

SEP 19 1966

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

15-47-19056-00-00

Operator's Full Name Spector Pipe & Supply, Inc.

Complete Address: Box 169 Russell, Kansas

Lease Name Brockett Well No. 1

Location NE NE SW Sec. 30 Twp. 1 Rge. 18 (E) (W) X

County Phillips Total Depth 3600'

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Lynch Casing Pulling Co.

Address: Great Bend, Kansas License No. 457

Operation Completed: Hour 12 P Day 15 Month 9 Year 1966

The Above well was plugged as follows:

Total Depth 3600' 8 5/8 csg set at 225' cwc 150 sc.

4 1/2 csg set at 3600 cw 150 sc cement.

Plug 3350' Sand to 3300' dumped 4 sc cement with dump bailer.

Recovered 1405' 4 1/2 csg.

Circ. 15 Sc gel mud at 600'

Set 25 sc cem. plug at 540'

Mud to 210' Set 20 Sc. cem. plug.

Mud to 40' Set 10' rock and 10 Sc cem. to base of celler.

I hereby certify that the above well was plugged as herein stated.

Signed: Leo Messing
Well Plugging Supervisor

INVOICED

DATE 9/19/66

INV. NO. 3939-W