



KANSAS

Form CP-3  
Rev. 6-26-62

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

RECEIVED  
STATE CORPORATION COMMISSION  
FEB 19 1969  
CONSERVATION DIVISION  
Wichita, Kansas

15-147-20063-00-00

Operator's Full Name Red Barron Productions

Complete Address: Phillipsburg, Kansas 67661

Lease Name Brockett Well No. 1

Location SE SW SW Sec. 30 Twp. 1 Rge. (E) (W) 18

County Phillips Total Depth 3565

Abandoned Oil Well      Gas Well      Input Well      SWD Well      D & A XX

Other well as hereafter indicated:     

Plugging Contractor: Red Tiger Drilling

Address: Wichita, Kansas License No.     

Operation Completed: Hour 6P Day 17 Month 2 Year 1969

The Above well was plugged as follows:

RTD 3565' 8 5/8 csg set at 226' cwc 140 sk. Cmt. Mat. 50-50 poz cmt. W/6% total gel.

Gunned pits, circulated heavy mud, set cementing plug at 600' and displaced 50 sk cmt

thru drill pipe. Heavy mud to 200' set cementing plug and displaced 25 sk cmt thru

drill pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulls and 10 sk cmt to base

of cellar. Plugged rat hole with 2 sk cmt.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo J. Maany  
Well Plugging Supervisor

DATE 2/19/69

INV. NO. 9353-4