

DISTRICT CONSERVATION AGENT'S REPORT

15-147-00114-00-00

B

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. 52-51

LOCATION SW SW SW

SEC. 30 TWP. 1 RGE. 18

Dry Hole Abandoned Oil Well x Abandoned Gas Well

I have today completed supervision of plugging of:

Well No. 1 Lease Brockett

Operator Lawrence & Meltzer Address Box 414 Great Bend, Kans

Field County Phillips

Total Depth 3540 Feet.

(Describe briefly the manner in which the well was plugged)

8 5/8' at 225' circulated with cement - 5 1/2" at 3559'

with 175 sax cement behind - Perforations at ~~3518~~ 3518'

Filled with sand to 3500', set 4 sax cement with dump bailer.

Pulled 600' 5 1/2", filled with mud to 225', set rock and

15 sax cement, mud to 35', set rock and 10 sax cement to

bottom cellar.

PLUGGING
FILE SEC 307-1-R-182
BOOK PAGE 52 LINE 31

RECEIVED
STATE CORPORATION COMMISSION
OCT 29 1952
CONSERVATION DIVISION
Wichita, Kansas

Edna Petty
District Conservation Agent
Date 10-22-52