

10
KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

~~15-~~111~~-20026-~~111~~-~~111~~~~
~~15-~~111~~~~
15-147-20026-00-00

RECEIVED
DEC 20 1967
DEC 20 1967
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Norman Fitzgerald
Complete Address: P. O. Box 5046 Abilene, Texas 79605
Lease Name Nelson Well No. 1
Location NE SW Sec. 33 Twp. 1 Rge. 20 (E) (W) X
County Phillips Total Depth 3978
Abandoned Oil Well Gas Well Input Well SWD Well D & A X
Other well as hereafter indicated:
Plugging Contractor: Red Tiger Drlg.
Address: Wichita, Kansas License No.
Operation Completed: Hour 5 A Day 17 Month 12 Year 1967

The Above well was plugged as follows:
RTD 3978' 8 5/8 csg set at 211' cwc 150 sc.
Gunned pits, circulated heavy mud, set cementing plug at 990' and displaced 100 sc cem,
thru drill pipe. Heavy mud to 210' set cementing plug and displaced 25 sc cement thru
drill pipe. Heavy mud to 40' set cementing plug, 1/2 sc hulls and 10 sc cement to base
of cellar. Plugged rat hole with 2 sc cement.

I hereby certify that the above well was plugged as herein stated.

INVOICED
DATE 12/20/67
INV. NO. 6946-11

Signed: Geo J. Massey
Well Plugging Supervisor