

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

15-053-30105-00-01

API Well Number: ~~15-053-00142-00-00~~
Spot: W2W2SE Sec/Twnshp/Rge: 31-16S-10W
1320 feet from S Section Line, 2310 feet from E Section Line
Lease/Unit Name: ROUS Well Number: 1
County: ELLSWORTH Total Vertical Depth: 3420 feet

Operator License No.: 6306
Op Name: BROWN, TOM CONSTRUCTION, INC.
Address: 109 MILLVIEW
SALINA, KS 67401

Production Casing Size: 5.5 feet: 3420
Surface Casing Size: 8.625 feet: 310 150 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/21/2003 9:15 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MONTE ANDREWS Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 938-2943

Proposed Plugging Method: ACCORDING TO THE RULES AND REGULATIONS OF THE STATE OF KANSAS.
RECEIVED
KCC DISTRICT #2
NOV 24 2003
WICHITA, KS

Plugging Proposal Received By: VIRGIL CLOTHIER Witness Type: Plugging Operations Partially Witnessed
Date/Time Plugging Completed: 11/21/2003 12:30 PM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:
Sand off perforations to 3290' and put 5 sacks of cement on top. Cut off 5-1/2" casing at 1760'. Pull to 1400' and pump 35 sacks of cement. Pull casing to 1050' and pump 35 sacks of cement. Pull casing to 360' and circulate cement to surface.
RECEIVED
KANSAS CORPORATION COMMISSION
NOV 25 2003
CONSERVATION DIVISION
WICHITA, KS

Remarks: COPELAND CEMENT TICKET #24017 60/40 POZ MIX WITH 4% GEL
Plugged through: CSG

District: 02
INVOICED
DATE 11-25-03
INV. NO. 2004060826

Signed Virgil Clothier
(TECHNICIAN)