

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: Southern Star Central Gas Pipeline
Address: 3800 Frederica Street Owensboro, Kentucky
Phone: (270) 852-5000 Operator License #: 33097
Type of Well: Gas Storage Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
The plugging proposal was approved on: September 17, 2003 (Date)
by: Jack Robison (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
Bush City Ss. Depth to Top: 508' Bottom: 555' T.D. 555'

Depth to Top: _____ Bottom: _____ T.D. _____

Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15-091-19069-00-00
Lease Name: Craig #14
Well Number: Craig # 14
Spot Location (QQQQ): NE SE SE
990' Feet from North / South Section Line
330' Feet from East / West Section Line
Sec. 22 Twp. 12 S. R. 23 East West
County: Johnson
Date Well Completed: 9/12/1924
Plugging Commenced: 10/31/2003
Plugging Completed: 10/31/2003

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
Bush City Ss. / Prod	Gas	3'	517'	6.625	cemented	517 0
Cond			36	8.250	36	0

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

All tubulars pulled from well-bore. Plugged solid with Class A cement, from surface to total depth.

Ran 2" to 550' pumped Class A to surface. SIP 500#.

Perforated 49'-50', 3 shts./ft.

Total Cement: 140 sks. Class A cement.

Name of Plugging Contractor: Splane Pulling & Roustabout Service License #: 6372

Address: P.O. Box 386 Chanute, Kansas 66270

Name of Party Responsible for Plugging Fees: Southern Star Central Gas Pipeline

State of Kentucky County, Daviess, ss.

Charles C. McConnell / D. Mark Rouse

(Employee of Operator) or (Operator) on above-described well, being first duly

sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) Charles C. McConnell / D. Mark Rouse

(Address) 3800 Frederica Street Owensboro, Kentucky 42304

SUBSCRIBED and SWORN TO before me this 4th day of December, 20 03

Karen J. Holman
Notary Public

My Commission Expires: 8-26-07

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202 B

RECEIVED
KANSAS CORPORATION COMMISSION
DEC 05 2003
CONSERVATION DIVISION
WICHITA, KS