

RECEIVED

FEB 10 2004

KCC WICHITA

STATE OF KANSAS
KANSAS CORPORATION COMMISSION
CONSERVATION DIVISION
130 South Market - Room 2078
Wichita, Kansas 67202

FORM CP-1 (3/92)

WELL PLUGGING APPLICATION FORM

(PLEASE TYPE FORM and File ONE Copy)

15-051-25250-00-00

API # 454-25250 (Identifier number of this well). This must be listed for wells drilled since 1967; if no API# was issued, indicate spud or completion date.

6/04

WELL OPERATOR Lario Oil & Gas Company KCC LICENSE # 5214

ADDRESS 301 S. Market (owner/company name) CITY Wichita (operator's)

STATE Kansas ZIP CODE 67202 CONTACT PHONE # () 316-265-5611

LEASE Schlegel WELL# 1-33 SEC. 33 T. 15 R. 17 (East/West)

~200' W of - NE - NW - NW SPOT LOCATION/0000 COUNTY Ellis

330 FEET (in exact footage) FROM S/N (circle one) LINE OF SECTION (NOT Lease Line)

790 FEET (in exact footage) FROM E/W (circle one) LINE OF SECTION (NOT Lease Line)

Check One: OIL WELL GAS WELL D&A SWD/ENHR WELL DOCKET# _____

CONDUCTOR CASING SIZE _____ SET AT _____ CEMENTED WITH _____ SACKS

SURFACE CASING SIZE 8-5/8" SET AT 1040' CEMENTED WITH 450 SACKS

PRODUCTION CASING SIZE 5-1/2" SET AT 3604' CEMENTED WITH 140 SACKS

LIST (ALL) PERFORATIONS and BRIDGEPLUG SETS: 3488' - 94' & 3498' - 3504'

ELEVATION 1889 / 1894 T.D. 3606' PBTD 3575' ANHYDRITE DEPTH _____
(G.L./K.B.) (Stone Corral Formation)

CONDITION OF WELL: GOOD POOR CASING LEAK JUNK IN HOLE

PROPOSED METHOD OF PLUGGING Sand off perms to 3420' & spot 5 sks cmt on top. Backoff & pull csg to set plugs as follows: 1700' w/ 110 sks + 300# hulls; 1030' w/ 40 sks + 200# hulls; Circ cement from 300' to surface.

Install swage & valve on well head. Call KCC 48 hrs prior to witness work. Cement is 60/40+10% gel+ 2% CC.

(If additional space is needed attach separate page)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? Yes IS ACO-1 FILED? No

If not explain why? _____ ACO-1 due 3/16/04

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

LIST NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Lario Oil & Gas Co. - Brad Sander PHONE# () 785-625-5023

ADDRESS P.O. Box 784 City/State Hays, KS 67601

PLUGGING CONTRACTOR Allied Cementing Co., Inc. KCC LICENSE # 99996

ADDRESS PO Box 31 Russell, KS 67665-0031 (company name) PHONE # () 785-483-2627 (contractor's)

PROPOSED DATE AND HOUR OF PLUGGING (If Known?) within 30 days

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT

DATE: 02/09/04 AUTHORIZED OPERATOR/AGENT: Jay S. Schwickert (signature)



CORPORATION COMMISSION

Kathleen Sebelius, Governor Brian J. Moline, Chair John Wine, Commissioner Robert E. Krehbiel, Commissioner

NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)

Lario Oil & Gas Company
301 South Market Street
Wichita, KS 67202

February 12, 2004

Re: SCHLEGEL #1-33
API 15-051-25250-00-00
NENWNW 33-15S-17W, 330 FNL 790 FWL
ELLIS COUNTY, KANSAS

Dear Operator:

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging.

Please contact the district office for approval of your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit.

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

District: #4
2301 E. 13th
Hays, KS 67601
(785) 625-0550

Sincerely


David P. Williams
Production Supervisor