

STATE OF KANSAS  
CORPORATION COMMISSION  
S. Market, Room 2078  
Wichita, KS 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

30105-00-01  
15-053-0042-00-06  
API NUMBER \_\_\_\_\_ Spud Date 1966

RECEIVED  
DEC 18 2003  
KCC WICHITA

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE NAME ROUS  
WELL NUMBER 1  
1320 Ft. from Ⓢ Section Line  
2310 Ft. from Ⓢ Section Line  
SEC. 31 TWP. 16 RGE. 10W (E) or (W)  
COUNTY Ellsworth  
Date Well Completed 2/15/95  
Plugging Commenced 11-20-03  
Plugging Completed 11-24-03

LEASE OPERATOR TOM BROWN CONSTRUCTION, INC.

ADDRESS 109 Millview Salina, Kansas 67401

PHONE(S) (785) 823-8223 OPERATORS LICENSE NO. 6306

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

A plugging proposal was approved on 11/4/03 (date)

Jack Luthi (KCC District Agent's Name).

ACO-1 filed? \_\_\_\_\_ If not, is well log attached? \_\_\_\_\_

Producing Formation \_\_\_\_\_ Depth to Top \_\_\_\_\_ Bottom \_\_\_\_\_ T.O. 3420'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
<u>Surf</u>				<u>8-5/8"</u>	<u>310'</u>	<u>None</u>
<u>Drill</u>				<u>5-1/2"</u>	<u>3420'</u>	<u>1760'</u>

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs are used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet each section. Plugged off bottom with sand to 3290' and 5 sacks cement. Cut pipe loose @1760', pulled up to 1400', pumped 35 sacks cement with 100# hulls, pulled up to 1050', pumped 35 sacks cement w/100# hulls, pulled up to 360' and circulated cement to surface. 60/40 pos. 4% gel. Plugging Complete

Name of Plugging Contractor Mike's Testing & Salvage, Inc. License No. 31529

Address P.O. Box 467 Chase, Kansas 67524

Name of Party Responsible for Plugging Fees: Tom Brown Construction, Inc.

State of Kansas County of Rice, ss.

Mike Kelso (Employee of Operator) or (Operator)

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts and statements, and matters herein contained and the log of the above-described well as filed to the same are true and correct, so help me God.

(Signature) [Signature]

(Address) P. O. Box 467 Chase, KS 67524

SUBSCRIBED AND SWORN TO before me this 17th day of December, 20 03

My Commission Expires:

