

KANSAS CORPORATION COMMISSION
CONSERVATION DIVISION
WICHITA STATE OFF. BUILDING
130 S MARKET ROOM 2078
WICHITA KS 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

15-125-19800.00.00

API NUMBER _____

LEASE NAME Rutland

WELL NUMBER OW-1

4085 Ft. from S Section Line

4760 Ft. from E Section Line

SEC 08 TWP 33 RGE 16 (E) or (x)

COUNTY Montgomery

Date Well Completed 10/15/03

Plugging Commenced 10/15/03

Plugging Completed 10/15/03

RECEIVED
DEC 24 2003
KCC WICHITA

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days

LEASE OPERATOR Kanmap Inc

ADDRESS 211 W. Myrtle, Independence KS 67301

PHONE # (620) 331-3140 OPERATORS LICENSE NO. 30451

Character of Well Gas

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 10/15/03 (Date)

by Tom Bilyeu (KCC District Agent's Name)

Is ACO - 1 filed ? NA If not, is well log attached ? no

Producing Formation Mississippi Depth to top +/- 1225 Bottom NA T.D. NA 1302

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
<u>Surf</u>		surf.	20'	8 5/8"	<u>cemented 20</u>	<u>surface</u>
<u>Mississippi</u>	<u>water</u>	surf.	1302'	4 1/2"	<u>cemented 1302</u>	<u>surface</u>

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet each set.

Ran in 2" pipe to 1195', circ. gel, spot 12 sks. cement, pull pipe up to 650', spot 12 sks. cement, pull pipe up to 350', circ cement to surf., pull pipe out, top off w/cement, dig out and cut casing, fill circ. pit, well plugged.

Total sks. cement - 64

RECEIVED

KCC District #3

(if additional description is necessary, use **BACK** of this form.)

Name of plugging contractor Rick's Well Service License No. 30849 33080

Address P.O. Box 268, Cherryvale, KS 67335

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES : Kanmap Inc.

STATE OF Kansas COUNTY OF Montgomery, ss.

(Employee of Operator) or (Operator) of Shanute KS
above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) [Signature]
(Address) _____

SUBSCRIBED AND SWORN TO before me this 19th day of Dec, 2003

[Signature]

Notary Public

My Commission Expires : 8/1-2005

Form CP - 4

