

RECEIVED

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION OIL & GAS CONSERVATION DIVISION WELL PLUGGING RECORD K.A.R. 82-3-117

FEB 18 2004

KCC WICHITA

Form CP-4 December 2003

Type or Print on this Form Form must be Signed All blanks must be Filled

Lease Operator: Webco Oil Company, Inc.

Address: 2136 NE 90th Ave., Hoisington, Ks. 67544

Phone: (620) 587-3539 Operator License #: 6357

Type of Well: Oil Docket #: (Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)

The plugging proposal was approved on: February 9th, 2004 (Date)

by: Pat Staab (KCC District Agent's Name)

Is ACO-1 filed? Yes No If not, is well log attached? Yes No

Producing Formation(s): List All (If needed attach another sheet)

Depth to Top: 3062' Bottom: 3280' T.D. 3317'

API Number: 15-009-22,336-00-00

Lease Name: Prosser

Well Number: #1

Spot Location (QQQQ): 100'S - NE - SE - SE

890 Feet from North / South Section Line

330 Feet from East / West Section Line

Sec. 33 Twp. 16 S. R. 12 East West

County: Barton

Date Well Completed: 05/07/1981 9/1/1981

Plugging Commenced: 02/12/04

Plugging Completed: 02/13/04

Show depth and thickness of all water, oil and gas formations.

Table with columns: Oil, Gas or Water Records (Formation, Content) and Casing Record (Surface Conductor & Production) (From, To, Size, Put In, Pulled Out). Includes handwritten entries for Surface and Production.

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole.

M.I.R.U. Run bailer to bottom. Fluid @550' from surface. Brackeen Line Cleaning brought water and sand off 266'. Rigged up jacks. Worked casing. Got approximately 5" of stretch - 1500' of pipe free. Spot 4 sx. cement on sand. Shut down for night. Checked stretch next day. Ran in hole with knife and cut casing @ 1650'. Pulled to 1425' - pumped 70 sx - 300# hulls. Pulled to 775' - pumped 40 sx - 100# hulls. Pull to 300' - pumped 55 sx. - 100# hulls. Pulled rest-hole stayed full. Rigged down & moved off.

Name of Plugging Contractor: D.S. & W. Well Servicing, Inc. License #: 6901

Address: P.O. Box 231, Claflin, Ks 67525

Name of Party Responsible for Plugging Fees: Webco Oil Company, Inc.

State of Kansas County, Barton, ss.

Edward S. Nemnich (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

KAREN J. MITCHELL Notary Public - State of Kansas My Appt. Expires 4/13/06

(Signature) Edward S. Nemnich (Address) P.O. Box 231, Claflin, Ks. 67525

SUBSCRIBED and SWORN TO before me this 16th day of February 20 04 My Commission Expires: 4/13/06

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202