

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION OIL & GAS CONSERVATION DIVISION WELL PLUGGING RECORD K.A.R. 82-3-117

RECEIVED

FEB 06 2004

KCC WICHITA

Form CP-4 December 2003 Type or Print on this Form Form must be Signed All blanks must be Filled

Lease Operator: BEREN CORPORATION

Address: P O BOX 20380

Phone: (316) 265-3311 Operator License #: 5364

Type of Well: ENHR Docket #: E-13,954 (Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)

The plugging proposal was approved on: 10/22/03 (Date)

by: STEVE PFEIFER (KCC District Agent's Name)

Is ACO-1 filed? Yes No If not, is well log attached? Yes No

Producing Formation(s): List All (if needed attach another sheet)

SIMPSON SD Depth to Top: 4,349 Bottom: 4,375 T.D. 4463

SIMPSON DOL Depth to Top: 4,329 Bottom: 4,336 T.D.

L-KC Depth to Top: 3,800 Bottom: 3,806 T.D.

API Number: 15-151-00080-00-01

Lease Name: (GRIER) (NRSU #2) Kolngsm-Simp

Well Number: (1) 2

Spot Location (QQQQ): - NE - NE - NE

Feet from North / South Section Line

Feet from East / West Section Line

Sec. 25 Twp. 27 S. R. 13 East West

County: PRATT

Date Well Completed: APRIL 1968

Plugging Commenced: 10/22/03

Plugging Completed: 10/23/03

Show depth and thickness of all water, oil and gas formations.

Table with columns: Oil, Gas or Water Records (Formation, Content) and Casing Record (Surface Conductor & Production) (From, To, Size, Put In, Pulled Out). Rows include SIMPSON Surf (OIL), L-KC Prod (WATER), and Prod (1349).

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole.

CIBP set at 4301'. Squeezed off L-KC perfs (3800-06) with 20 sxs cmt, 50# hulls, and 10 sxs gel. Pumped to bottom. Shot pipe off at 1300', pulled to 800', pumped 50 sxs cement and 50# hulls. Pulled pipe to 350' - pumped 70' sxs cement. Pulled pipe to 40', pumped 20 sxs circ to surface. Pulled out pipe. Cement dropped 150' in pipe. Will come back & toP off.

Name of Plugging Contractor: BEREXCO, INC Beren Corp License #: 5363 99998


Address: P O BOX 20380, WICHITA, KS 67208

Name of Party Responsible for Plugging Fees: BEREN

State of KANSAS County, SEDGWICK, ss.

GARY MISAK (Employee of Operator) or (Operator) on above-described well, being first duly

sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.



(Signature) Gary Misak

(Address) P O BOX 20380, WICHITA, KS 67208

SUBSCRIBED and SWORN TO before me this 3RD day of FEBRUARY, 2004

(Signature) Diana E Plotner My Commission Expires: Aug 10, 2007 Notary Public

OCT 29 2003

*Well File*

**United Cementing & Acid Company, Inc.**

2510 W. 6th St.

El Dorado, Kansas 67042

316-321-4680 800-794-0187 (Fax) 316-321-4720

Remit Payment To:

One North Hudson, Suite 1000

Oklahoma City, OK 73102

405-278-8800

Customer:

Berexco. Inc.  
PO Box 20380  
Wichita, Kansas 67208

**RECEIVED**

**FEB 06 2004**

**KCC WICHITA**

Invoice No. 5591  
Field Ticket 5042  
Date 10/27/2003  
PO#

*(Circle #1)*

Date of Job	County	State	Lease	Well No.
10/23/03	PR	KS	NRSU	#2 SWD
Size of Casing	Depth Of Well	Depth Of Job	Plug Depth	Pressure
Quantity	Description	UOM	Unit Price	Total
	<b>OLD HOLE PLUG</b>			
160	60/40 Pozmix	sax	4.90	784.00
20	Gel	sax	9.70	194.00
150	Cottonseed Hulls	cwt	14.90	22.35
180	Bulk Charge	sax	0.98	176.40
	Drayage - MINIMUM CHARGE			94.50
70	Pump Truck Mileage Charge	mi	2.05	143.50
	Cement Unit			482.00
<i>WO P&amp;D well</i>				
<i>Thank you for your continued business</i>				
	<b>Taxable</b>	<b>*Non-Taxable</b>	<b>Tax Rate</b>	<b>Sales Tax</b>
	1896.75	0.00	0.063	119.50
				<b>TOTAL DUE</b>
				<b>\$2,016.25</b>

TERMS: Net 30 days from invoice date. Please pay from this invoice.

ORIGINAL INVOICE



# United Cementing and Acid Co., Inc.

RECEIVED  
 FEB 06 2004  
 SERVICE TICKET  
 5042

Oil Well Cementing & Acidizing  
 (316) 321-4680 • 800-794-0187 • FAX (316) 321-4720  
 2510 West 6th Street • El Dorado, KS 67042

DATE 10-23-03

COUNTY Pratt CITY \_\_\_\_\_

CHARGE TO BEREXCO

ADDRESS \_\_\_\_\_ CITY \_\_\_\_\_ ST \_\_\_\_\_ ZIP \_\_\_\_\_

LEASE & WELL NO. DR50 #2 SWD CONTRACTOR Co. Tools

KIND OF JOB Old hole plugging SEC. \_\_\_\_\_ TWP. \_\_\_\_\_ RNG. \_\_\_\_\_

DIR. TO LOC. 2 East, 2 north of Pratt  OLD  NEW

Quantity	MATERIAL USED	Serv. Charge	
1605x	60/40 poz @ 4.90/		482.00/
205x	GEL @ 9.70		784.00/
150 lbs	COTTON SEED HULLS @ 14.90 cwt.		194.00
			22.35
1805x	BULK CHARGE		176.40
MIN	BULK TRK. MILES		94.50
70	PUMP TRK. MILES		143.50/
	PLUGS		
		.0630 SALES TAX	119.50
		TOTAL	2016.25

T.D. \_\_\_\_\_ CSG. SET AT \_\_\_\_\_ VOLUME \_\_\_\_\_  
 SIZE HOLE \_\_\_\_\_ TBG SET AT \_\_\_\_\_ VOLUME \_\_\_\_\_  
 MAX. PRESS. \_\_\_\_\_ SIZE PIPE \_\_\_\_\_  
 PLUG DEPTH \_\_\_\_\_ PKER DEPTH \_\_\_\_\_  
 PLUG USED \_\_\_\_\_ TIME FINISHED \_\_\_\_\_

REMARKS: Mix & pump 1/25X CSH & 205X 60/40 poz 6% gel with 1/25X CSH & disp. cement to 3103ft, to 3800ft, & held psi. Then shut 2 7/8 tubing at 1310ft. & pulled up to 800ft. Mix & pump 105X gel in 30 bbl water, mix & pump 505X 60/40 poz 6% gel & disp. pulled up to 350ft mix & pump 705X 60/40 poz 6% gel & disp. pulled up to 40ft. mix & pump 205X to surface.

EQUIPMENT USED

NAME	UNIT NO.	NAME	UNIT NO.
<u>Chat Johnson P-14</u>		<u>Phillip Malone B-3</u>	
<u>James Thomas #44</u>			
CEMENTER OR TREATER		OWNER'S REP.	