

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
S. Market, Room 2078  
Wichita, KS. 67202

K.A.R.-82-3-117

API NUMBER 15-151-20,316-00-00

LEASE NAME SHRIVER

WELL NUMBER 1

330 Ft. from S Section Line

1320 Ft. from <sup>W</sup> Section Line  
~~3960~~

SEC. 26 TWP. 29 RGE. 14 (X) or (Y)

COUNTY PRATT

Date Well Completed 1-13-76

Plugging Commenced 1-12-2004

Plugging Completed 1-12-2004

RECEIVED

JAN 16 2004

KCC WICHITA

LEASE OPERATOR MAI OIL OPERATIONS, INC.

ADDRESS P.O. BOX 33, RUSSELL, KS. 67665

PHONE (785) 483 2169 OPERATORS LICENSE NO. 5259

Operator of Well GAS

(i.e., Gas, D&A, SWD, Input, Water Supply Well)

A plugging proposal was approved on 1-8-2004 (date)

STEVE DURRANT (KCC District Agent's Name).

ACO-1 filed? NO If not, is well log attached? NO

Producing Formation \_\_\_\_\_ Depth to Top \_\_\_\_\_ Bottom T.O. 4575

Record the depth and thickness of all water, oil and gas formations.

LOGS, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in Well	Pulled out
<u>Surf</u>		<u>241'</u>	<u>0</u>	<u>10 3/4"</u>	<u>CMFD W/25 SKS</u>	<u>NONE</u>
<u>Prod</u>		<u>394'</u>	<u>0</u>	<u>4 1/2"</u>	<u>CMFD W/75 SKS</u>	<u>NONE</u>
<u>Prod</u>		<u>394'</u>		<u>4 1/2"</u>	<u>394'</u>	<u>0</u>

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug material is used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet each set  
OUTSIDE OF 4 1/2" @ 1036' RUN TBG. TO 893' MIX 175 SKS 60-40-POZ 6% GEL & 500# HULLS. CEMENT TO SURFACE. PULL TBG. HOOKUP TO 10 3/4" BRADENHEAD MIX 25 SKS 60-40 POZ 6% GEL & 75 SKS COMMON 2% GEL, 3% CCMAX PSI 250# ISIP & STANDING PSI 125# FILL UP 4 1/2" W/25 SKS COMMON.

Name of Plugging Contractor ALLIED CEMENTING Pratt Well Serv. Co License No. 5893

Address P.O. BOX 31, RUSSELL, KS. 67665

Name of Party Responsible for Plugging Fees: MAI OIL OPERATIONS, INC.

State of KANSAS COUNTY OF RUSSELL, ss.

ALLEN BANGERT

(Employee of Operator) or (Operator) of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts and circumstances, and matters herein contained and the log of the above-described well as filed the same are true and correct, so help me God.

(Signature) Allen Bangert

(Address) \_\_\_\_\_

SUBSCRIBED AND SWORN TO before me this 13 day of January, 2004

Anita G. Driscoll  
Notary Public

My Commission Expires:



Form CP-4  
Revised 05-88

# KANSAS

## CORPORATION COMMISSION

KATHLEEN SEBELIUS, GOVERNOR  
BRIAN J. MOLINE, CHAIR  
JOHN WINE, COMMISSIONER  
ROBERT E. KREHBIEL, COMMISSIONER

January 20, 2004


Mai Oil Operations, Inc.  
PO Box 33  
Russell, Ks 67665

RE: Request for Change of Operator, Form T-1  
API Well No. **15-151-20316-00-00**  
**SHRIVER 1**  
**26-29-14W, 330 FSL 3960 FEL**  
**PRATT**, County, Kansas

To Whom It May Concern:

According to Commission records **TRI K VENTURES, INC.** is the current operator of record for the above referenced lease. On **January 20, 2004**, a well plugging record (CP-4) was received on the **SHRIVER #1** well. A file review failed to show that **TRI K VENTURES, INC.** has filed a transfer form for the referenced lease. If the lease was transferred but a T-1 was not filed, please complete the enclosed form with original signatures from both parties and file the form with the Corporation Commission at the address listed on the form. If operator responsibility has remained with **TRI K VENTURES, INC.**, please inform me immediately at (316) 337-6225.

Sincerely,

  
Barbara Montgomery  
Production Department

Enclosures

*Copy*