

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-22754-00-00
Spot: SWNE Sec/Twnshp/Rge: 15-14S-17W
3300 feet from S Section Line, 1980 feet from E Section Line
Lease Name: CHRISTINA Well #: 5
County: ELLIS Total Vertical Depth: 3635 feet

Operator License No.: 5363
Op Name: BEREXCO, INC.
Address: PO BOX 20380
WICHITA, KS 67208

PROD Size: 5.5 feet: 3634 w/125 sxs cmt
SURF Size: 8.625 feet: 252 w/150 sxs cmt

#118¹⁴

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 02/09/2004 9:00 AM
Plug Co. License No.: 99998 Plug Co. Name: COMPANY TOOLS
Proposal Rcvd. from: CURT GABEL Company: BEREXCO, INC. Phone: (785) 628-6101

Proposed Plugging Method: Ordered out 300 sxs 60/40 pozmix - 10% gel - 600# hulls.
Well squeezed at 600' w/200 sxs cement.

Plugging Proposal Received By: JAY PFEIFER WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 02/09/2004 2:00 PM KCC Agent: JAY PFEIFER

Actual Plugging Report:

Perfs:

TIH with tubing to 3500' - mixed and pumped 100 sxs cement with 400# hulls.
Pulled up to 2000' - spotted 100 sxs cement.
Pulled up to 500' - circulated cement with 50 sxs.
Swaged onto 5 1/2" - topped with 15 sxs cement. S.I.P. 200#.
Hooked to the annulus and pumped 25 sxs cement.
S.I.P. 250#.

RECEIVED
FEB 13 2004
KCC WICHITA

Remarks: LEASE ALSO KNOWN AS SCHMIDTBERGER #1 AND BOLLIG #1. ALLIED CEMENTING COMPANY.

Plugged through: TBG

District: 04

Signed _____

Jay Pfeifer

(TECHNICIAN)

INVOICED

DATE

2-13-04

INV. NO.

2004061179

FEB 10 2004