

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-047-21343-00-00
Spot: S2S2SE Sec/Twnshp/Rge: 5-24S-17W
330 feet from S Section Line, 1320 feet from E Section Line
Lease Name: CARPENTER 5 Well #: 2
County: EDWARDS Total Vertical Depth: 4540 feet

Operator License No.: 5056
Op Name: HOLL, F.G., COMPANY L.L.C.
Address: 9431 E CENTRAL, SUITE 100
WICHITA, KS 67206

PROD Size: 4.5 feet: 4538 WITH 250 SX CMT
SURF Size: 8.625 feet: 310 WITH 225 SX CMT

#147⁵⁵

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 02/02/2004 1:00 PM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 278-2026

Proposed Plugging Method: SAND TO 4265' & 4 SX CMT. PLUG AT 1250' WITH 15 SX GEL- 300#HULLS - 50 SX CMT. PLUG AT 600' WITH 100# HULLS & 50 SX CMT. PLUG AT 330' WITH 50 SX CMT. PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: KEVIN STRUBE WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 02/02/2004 5:28 PM KCC Agent: RICHARD LACEY

Actual Plugging Report:

PBTD 4487'. ANHYDRITE @ 1171-1191'. SANDED TO 4265' & DUMPED 4 SX CMT ON TOP OF SAND WITH BAILER. PUMPED PLUGS THROUGH CASING. 1ST PLUG AT 1250' WITH 20 SX GEL - 300# HULLS & 50 SX CMT. 2ND PLUG AT 600' WITH 100# HULLS & 50 SX CMT. 3RD PLUG AT 330' WITH 50 SX CMT. 4TH PLUG AT 40' WITH 10 SX CMT.

Perfs:


Top	Bot	Thru	Comments
4354	4364		
4338	4349		

RECEIVED
FEB 13 2004
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 2425' OF 4 1/2" CASING.

Plugged through: CSG

District: 01



Signed

Richard W. Lacey
(TECHNICIAN)

INVOICED
DATE 2-13-04
NO. 2004061184

Form CP