

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-22509-00-00
Spot: SENESE Sec/Twnshp/Rge: 33-16S-12W
1650 feet from S Section Line, 330 feet from E Section Line
Lease Name: PROSSER Well #: 2
County: BARTON Total Vertical Depth: 3321 feet

Operator License No.: 6357
Op Name: WEBCO OIL CO., INC.
Address: 2136 NE 90 AVE.
HOISINGTON, KS 67544

CIBP Size: feet: 3300
CIBP Size: feet: 3317
PROD Size: 5.5 feet: 3319 175 ASSUMED
SURF Size: 8.625 feet: 360 260 SX CMT

#107⁹³

Well Type: OIL UIC Docket No: Date/Time to Plug: 02/11/2004 11:15 AM
Plug Co. License No.: 6901 Plug Co. Name: D S & W WELL SERVICING, INC.
Proposal Rcvd. from: BRIAN SCHMACHER Company: D S & W WELL SERVICING, INC. Phone: (620) 587-3361

Proposed Plugging Method: Orderd 225 sxs 60/40 pozmix - 10% gel - 500# hulls.

Plugging Proposal Received By: PAT STAAB WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 02/11/2004 2:00 PM KCC Agent: PAT STAAB

Actual Plugging Report:

D.S.& W. sanded bottom to 3000' with 5 sxs cement on top using a dump bailer.
Shot casing at 1550' - pulled to 1425' - pumped 100 sxs 60/40 pozmix with 300# hulls mixed in.
Pulled casing to 775' - pumped 50 sxs 60/40 pozmix with 100# hulls.
Pulled casing to 300' - pumped 65 sxs 60/04 pozmix with 100# hulls.
Circulated cement to surface. POOH.
Pulled rest of casing and topped with 10 sxs cement .
Hole standing full.

Perfs:

Top	Bot	Thru	Comments
3315	3316		
3262	3270		
3076	3077		
3062	3063		
2973	2975		

RECEIVED
FEB 13 2004
KCC WICHITA

Remarks: COPELAND ACID AND CEMENTING COMPANY-TICKET #24110.

Plugged through: CSG

District: 04

(Signature)

Signed *(Signature)*
(TECHNICIAN)

INVOICED
DATE 2-13-04
INV. NO. 2004061190

FEB 12 2004

11/21/81

REPLACEMENT CARD

REIF OIL OPERATIONS, INC. #2 PROSSER 100'S. 10' L.W.

Box 298

HOUSTON, KS 67544 C. SE NE SE

CONTR. DUKE DRILLING COMPANY INC CTY. BARTON

GEOL. JIM MUSGROVE FIELD ODIN

ELV. 1864 KB SPD 9/14/81 CARD ISSUED 5/20/82 IP P 20 BOPD

SP. 15-009-22,509 LKC 3262-3270 (NEW PAY)

+	+	+
+	+	+
+	+	+

SMP	Tops	Depth/Datum
ANH	747	+1117
B ANH	768	+1096
HEEB	2954	-1090
TOR	2971	-1107
DOUG	2982	-1118
BR LM	3043	-1179
LANS	3058	-1194
BKC	3304	-1440
CONG SD	3315	-1451
ARB	3317	-1453
RTD	3321	-1457

8-5/8" 360; 5 1/2" 3319

NO DSTS

MICT. CO. (ARB OH), SWB 1/2 BOPH, NW, NAT, AC 250G, SWB LD & REC ALL WTR, SET BP AT 3317; PF (CONG SD) 3315-16; SWB 1/2 BOPH, DECL TO 1/4 BOPH; NAT, AC 250G, NO INCR; SET BP AT 3300, PF (LKC) 3262-70; SWB GSO, NAT, AC 1500G, SWB DWN, POP, P 20 BOPD

CORRECTION: 3/3/83 - ORIGINALLY FIRST REPORTED IN 100'S, C SE, NE, NE

NOTE: INFO RELEASED 6/24/82 - WAS OIL WELL - TIGHT HOLE