

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-175-10123-00-01
Spot: NWSW Sec/Twnshp/Rge: 36-33S-31W
1980 feet from S Section Line, 4620 feet from E Section Line
Lease/Unit Name: BLACK GENE OWWO Well Number: 1
County: SEWARD Total Vertical Depth: 5905 feet

Operator License No.: 30606
Op Name: MURFIN DRILLING CO., INC.
Address: 250 N. WATER, STE 300
WICHITA, KS 67202

Production Casing Size: 7 feet: 5905 WITH 275 SX CMT
Surface Casing Size: 9.625 feet: 1247 WITH 660 SX CMT

#19191

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 12/03/2003 9:00 AM
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.
Proposal Rcvd. from: JAMES ESQUIVEL Company: MURFIN DRILLING CO., INC. Phone: (620) 277-0562

Proposed Plugging Method: SET CIBP @ 1300'. PRESSURE TEST 7". PERFORATE AT 1250'. CIRCULATE CMT TO SURFACE.

Plugging Proposal Received By: KEVIN STRUBE WitnessType: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 12/03/2003 4:00 PM KCC Agent: JIM HOLLAND

Actual Plugging Report:


PBTD 5680'. PERFS AT 5575-80'. SHOOT 2 3/8" TUBING OFF AT 4250'. PULL 1 JOINT & PUMP 30 SX CMT. PULL OUT OF HOLE WITH TUBING & LAY DOWN. SET CIBP @ 1300'. LOAD HOLE WITH FRESH WATER. PRESSURE TEST 7" TO 300 PSIG. PERFORATE AT 1250'. PUMP 380 SX CMT TO FILL 7" & 7" X 9 5/8" ANNULUS FROM 1250' TO SURFACE.

RECEIVED
DEC 09 2003
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY ACID SERVICES. NO CASING RECOVERED.

Plugged through: CSG

District: 01



Signed

Jim Holland
(TECHNICIAN)

INVOICED

DATE

12.9.03

NO. NO.

2004060582

FORM SP-2/3
