

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-055-21583-00-01  
Spot: S2SESE Sec/Twnshp/Rge: 7-23S-34W  
330 feet from S Section Line, 4620 feet from W Section Line  
Lease Name: MEEKER A Well #: 3  
County: FINNEY Total Vertical Depth: 5000 feet

Operator License No.: 5447  
Op Name: OXY USA, INC.  
Address: PO BOX 27570 5 E GREENWAY PLZ  
HOUSTON, TX 77227

CIBP Size: feet: 3300 WITH 2 SX CMT  
MSCC Size: feet: 3319 CMT ABOVE 340'  
PROD Size: 5.5 feet: 4974 WITH 450 SX CMT  
SURF Size: 8.625 feet: 1763 WITH 510 SX CMT

*8/62<sup>50</sup>*

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 01/22/2004 12:00 PM

Plug Co. License No.: 31151 Plug Co. Name: SARGENT AND HORTON PLUGGING, INC.

Proposal Rcvd. from: DON HORTON Company: SARGENT AND HORTON PLUGGI Phone: (580) 854-6515

Proposed Plugging Method: PUMP 300# HULLS & 25 SX CMT. MUD SPACER TO 1800'. PUMP 80 SX CMT AT 1800'. CMT FROM 500' TO SURFACE. CHECK BACKSIDE.

Plugging Proposal Received By: KEVIN STRUBE

WitnessType: COMPLETE (100%)

Date/Time Plugging Completed: 01/22/2004 4:00 PM

KCC Agent: KEVIN STRUBE

Actual Plugging Report:

PBTD 4934'. PUMPED DOWN 5 1/2" 300# HULLS & 24 SX CMT. 1ST PLUG MUD SPACER TO 1800'. PUMPED 80 SX CMT AT 1800'. 2ND PLUG MUD SPACER TO 500' CEMENTED WITH 70 SX CMT FROM 500' TO 0'. PUMPED DOWN 8 5/8" X 5 1/2" ANNULUS WITH 5 SX CMT. PRESSURED UP TO 500 PSIG.

Perfs:


Top	Bot	Thru	Comments
2794	2824		

RECEIVED  
FEB 13 2004  
KCC WICHITA

Remarks: USED COMMON CEMENT BY SARGENTS. NO CASING RECOVERED.

Plugged through: CSG

District: 01



Signed

*Kevin D Strube*

(TECHNICIAN)

INVOICED

DATE 2-13-04  
BY 2004061186

Form *[Signature]*