

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-055-20507-00-00  
Spot: SENW Sec/Twnshp/Rge: 28-23S-34W  
3300 feet from S Section Line, 3300 feet from E Section Line  
Lease Name: GARDEN CITY D Well #: 2  
County: FINNEY Total Vertical Depth: 4950 feet

Operator License No.: 5447  
Op Name: OXY USA, INC.  
Address: PO BOX 27570 5 E GREENWAY PLZ  
HOUSTON, TX 77227

CIBP Size: feet: 4700 WITH 2 SX CMT  
COND Size: 21 feet: 40 WITH 4 YDS CMT  
MSCC Size: feet: 3350  
PROD Size: 5.5 feet: 4948 WITH 350 SX CMT  
SURF Size: 8.625 feet: 1931 WITH 900 SX CMT

*Handwritten:* \$16088

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 01/21/2004 9:30 AM  
Plug Co. License No.: 31151 Plug Co. Name: SARGENT AND HORTON PLUGGING, INC.  
Proposal Rcvd. from: DON HORTON Company: SARGENT AND HORTON PLUGGI Phone: (580) 854-6515

Proposed Plugging Method: PUMP 300# HULLS & 25 SX CMT. PLUG AT 1950' WITH 50 SX CMT. PLUG AT 1100' WITH 50 SX CMT. PLUG AT 600' WITH 30 SX CMT. PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: KEVIN STRUBE WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 01/21/2004 4:30 PM KCC Agent: KEVIN STRUBE

Actual Plugging Report:

PBTD 4891'. PUMPED DOWN 5 1/2" WITH 300# HULLS & 25 SX CMT. DISPLACED WITH 56 BBL MUD. 1ST PLUG PULLED UP TO 1950'. CIRCULATED HOLE WITH MUD & PUMPED 50 SX CMT. 2ND PLUG PULLED UP TO 1100' & PUMPED 50 SX CMT. 3RD PLUG PULLED UP TO 600' & PUMPED 30 SX CMT. 4TH PLUG PULLED TO 40' & PUMPED 10 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4742	4758		
2792	2852		

RECEIVED  
FEB 13 2004  
KCC WICHITA

Remarks: USED COMMON CEMENT BY SARGENTS. RECOVERED 2238' OF 5 1/2" CASING.

Plugged through: CSG

District: 01

RECEIVED  
FEB - 2 2004  
KCC Dodge City

Signed Kevin D Strub  
(TECHNICIAN)  
INVOICED  
DATE 2-13-04  
2004061186

Form *[Signature]*