

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-187-20819-00-00
Spot: SESW Sec/Twnshp/Rge: 35-29S-40W
660 feet from S Section Line, 1980 feet from W Section Line
Lease Name: MITCHELL, GRETA Well #: 1-35
County: STANTON Total Vertical Depth: 5739 feet

Operator License No.: 5952
Op Name: BP AMERICA PRODUCTION COMPANY
Address: 2225 WEST OKLAHOMA AVENUE
ULYSSES, KS 67880

CIBP Size: feet: 5600
CIBP Size: feet: 5644
MSCC Size: feet: 2977 WITH 220 SX CMT
PROD Size: 4.5 feet: 5739 WITH 460 SX CMT
SURF Size: 8.625 feet: 1713 WITH 650 SX CMT

#186.52

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 02/11/2004 10:00 AM
Plug Co. License No.: 99997 Plug Co. Name: HALLIBURTON ENERGY SERVICES
Proposal Rcvd. from: JOE EUDEY Company: BP AMERICA Phone: (620) 356-6955

Proposed Plugging Method: CIBP @ 5600' WITH 2 SX CMT. CIRCULATE CMT TO SURFACE.

Plugging Proposal Received By: RICHARD LACEY Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 02/11/2004 12:00 PM KCC Agent: KEVIN STRUBE

Actual Plugging Report:

PBTD 5698'. SET CIBP @ 5600' WITH 2 SX CMT. BOND LOG. TOC @ 1570'.
PERFORATED AT 600'. PUMPED WATER DOWN 4 1/2" AND ESTABLISHED
CIRCULATION. MIX CMT & CIRCULATED CMT TO SURFACE WITH 145 SX CMT.

Perfs:


Top	Bot	Thru	Comments
5647	5655		
5631	5639		

RECEIVED
FEB 13 2004
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY HALLIBURTON. NO CASING RECOVERED.

Plugged through: CSG

District: 01



Signed

Kevin D. Strube

INVOICE
DATE 2-13-04
NOV. 2004 06/18/