

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

JUN 1 1970

CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

15-147-20096-00-00

Operator's Full Name Petroleum Management, Inc.

Complete Address 1515 KSB&T Bldg., Wichita, Ks.

Lease Name Harrison Well No. 1

Location NW NW NE Sec. 5 Twp. 1 Rge. (E) (W) 16

County Phillips Total Depth 210' 3555'

Abandoned Oil Well Gas Well Input Well SWD Well D & A XX

Other well as hereafter indicated

Plugging Contractor Red Tiger Drlg.

Address Wichita, Ks. License No.

Operation Completed: Hour 8P Day 28 Month 5 Year 1970

The above well was plugged as follows:
RTD 3555' 8 5/8 csg set at 210' cwc Cmt mat 100 sk reg poz 6% gel.
Gunned pits, circulated heavy mud, set cementing plug at 540' and displaced 70 sk cmt
thru drill pipe. Heavy mud to 180' set cementing plug and displaced 20 sk cmt thru
drill pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulls and 10 sk cmt to base
of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: Scott Manning
Well Plugging Supervisor

INVOICED

DATE 6/1/70
INV. NO. 1978-11