



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

15-183-20001-00-00

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
FEB 16 1971  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Sliv Fickel of Red Tiger Drilling Company has this date requested permission to plug the following described well:

Mr. Rolfe D. Reber guarantees payment of the plugging fee.

Operator's full Name: Petroleum Management, Inc.

Complete Address: 1515 Vickers KSB-T.Bldg., Wichita, Kansas 67202

Lease Name: Overmiller Well No. # 1

Location: SE SE SE Sec. 4 Twp. 1 Rge. 13 (E)(W) W

County: Smith Total Depth 3835 Oil Well     

Gas Well      Input Well      SWD Well      D & A X Lost Hole     

Mr. Sliv Fickel was instructed to plug the well as follows:

8 5/8" 210' Cwc.

Circulated hole with heavy mud to 500', set plug, & displaced 50 sax

cement thru drill pipe. Mud to 200' & displaced 25 sax cement thru

drill pipe. Mud to 40', 1/2 sax hulls, plug, & displaced 10 sax

cement with Halliburton Cementing Company's pump truck, cementing

to base of cellar.

Very truly yours,

Don Luman  
Conservation Division Agent