



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

15-147-20096-00-00

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Fickle of Red Tiger has this date requested permission to plug the following described well:

Mr. Fickle guarantees payment of the plugging fee.

Operator's full Name: Petroleum Management, Inc.

Complete Address: 1515 KSB&T Bldg., Wichita, Kansas

Lease Name: Harrison Well No. 1

Location: NW NW NE Sec. 5 Twp. 1 Rge. (E)(W) 16

County: Phillips Total Depth 3555 Oil Well

Gas Well  Input Well  SWD Well  D & A XX Lost Hole

Mr. Fickle was instructed to plug the well as follows:  
Gun pits, circulate heavy mud, set cementing plug at 540' and displace  
70 sk cmt thru drill pipe. Heavy mud to 180' set cementing plug and  
displace 20 sk cmt thru drill pipe. Heavy mud to 40' set cementing  
plug, 1/2 sk hulls and 10 sk cmt to base of cellar.

Very truly yours,

Les F. Massey  
Conservation Division Agent