

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-025-21183-00-00
Spot: NWSESE Sec/Twnshp/Rge: 6-35S-25W
990 feet from S Section Line, 990 feet from E Section Line
Lease Name: THEIS 6 Well #: 3
County: CLARK Total Vertical Depth: 6300 feet

Operator License No.: 5278
Op Name: E.O.G. RESOURCES INC.
Address: 20 N. BROADWAY #800
OKLAHOMA CITY, OK 73102

CIBP Size: feet: 5903 WITH 2 SX CMT
PROD Size: 4.5 feet: 6300 WITH 240 SX CMT
SURF Size: 8.625 feet: 818 WITH 400 SX CMT

#204 TS

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 02/09/2004 9:00 AM
Plug Co. License No.: 33338 Plug Co. Name: ORR ENTERPRISES, INC.
Proposal Rcvd. from: RONNIE ORR Company: ORR ENTERPRISES, INC. Phone: (580) 251-9618

Proposed Plugging Method: CIBP @ 5903' & 2 SX CMT. RUN TUBING TO 838' & PUMP 75 SX CMT. FILL 8 5/8" WITH MUD & CMT TO SURFACE.

Plugging Proposal Received By: STEVE DURRANT Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 02/03/2004 10:30 AM KCC Agent: STEVE DURRANT

Actual Plugging Report:

CIBP @ 5903 & 2 SX CMT ON TOP OF PLUG. 1ST PLUG RAN 2 3/8" TUBING TO 838' MIX & PUMP 75 SX CLASS C CEMENT. PULL OUT OF HOLE AND WAIT ON CEMENT. TAG PLUG AT 615'. 2ND PLUG FILL 8 5/8" TO 40' WITH MUD & CMT TO SURFACE WITH 10 SX CMT.

Perfs:


Top	Bot	Thru	Comments
5953	6055		

RECEIVED
FEB 13 2004
KCC WICHITA

Remarks: USED CLASS C CEMENT BY ORR ENTERPRISES. RECOVERED 1760' OF 4 1/2" CASING.

Plugged through: TBG

District: 01



Signed

Steve Hurmont
(TECHNICIAN)

INVOICED
DATE 2-13-04
WV. NO. 2004061183