

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-185-13188-00-00  
Spot: E2E2SE Sec/Twnshp/Rge: 7-21S-11W  
1320 feet from S Section Line, 330 feet from E Section Line  
Lease Name: SCHLOCHTERMEIER B-7 Well #: 2  
County: STAFFORD Total Vertical Depth: 3485 feet

Operator License No.: 5056  
Op Name: HOLL, F.G., COMPANY L.L.C.  
Address: 9431 E CENTRAL, SUITE 100  
WICHITA, KS 67206

PROD Size: 5.5 feet: 3484  
SURF Size: 8.625 feet: 258

*\$113<sup>20</sup>*

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 02/18/2004 2:00 PM  
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.  
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 278-2026

Proposed  
Plugging  
Method:

PUMP CMT DOWN TUBING & CIRCULATE TO SURFACE. CHECK BACKSIDE.

Plugging Proposal Received By: RICHARD LACEY Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 02/18/2004 3:57 PM KCC Agent: RICHARD LACEY

Actual Plugging Report:

TRIED TO WORK TUBING THROUGH A BRIDGE. COULD NOT GET TUBING PAST 490' DUE TO COLLAPSED CASING. PUMPED 225 SX CMT DOWN TUBING CIRCULATING CMT TO SURFACE UP 5 1/2". NO CIRCULATION UP 8 5/8' X 5 1/2" ANNULUS. PUMPED 15 SX CMT DOWN 8 5/8" X 5 1/2" ANNULUS MAXIMUM PRESSURE 250 PSIG. PULLED TUBING & TOPPED OFF 5 1/2" WITH 15 SX CMT.

RECEIVED  
FEB 23 2004  
KCC WICHITA


Perfs:

Top	Bot	Thru	Comments
3444	3448		

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. NO CASING RECOVERED.

Plugged through: TBG

District: 01



Signed Richard W. Lacey

(TECHNICIAN)

INVOICED  
DATE 2-24-04  
INV. NO. 2004061210

Form CP 1/8  
*[Signature]*