

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-129-21494-00-01  
Spot: N2SWNW Sec/Twnshp/Rge: 23-33S-41W  
1850 feet from N Section Line, 660 feet from W Section Line  
Lease Name: USA BARKER A Well #: 2H  
County: MORTON Total Vertical Depth: 5665 feet

Operator License No.: 4549  
Op Name: ANADARKO PETROLEUM CORPORATI  
Address: 1201 LAKE ROBBINS DRIVE  
THE WOODLANDS, TX 77380

CIBP Size: feet: 2160  
CIBP Size: feet: 2300  
MSCC Size: feet: 2424 WITH 115 SX CMT  
PROD Size: 5.5 feet: 4330 WITH 105 SX CMT  
SURF Size: 8.625 feet: 1410 WITH 365 SX CMT

*184"*

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 02/12/2004 1:00 PM  
Plug Co. License No.: 31151 Plug Co. Name: SARGENT AND HORTON PLUGGING, INC.  
Proposal Rcvd. from: JOHN Company: SARGENT AND HORTON PLUGGI Phone: (580) 854-6515

Proposed Plugging Method: PUMP 200# HULLS & 25 SX CMT. PLUG AT 1450' WITH 50 SX CMT. PLUG AT 500' WITH 30 SX CMT. PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: STEVE MIDDLETON WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 02/13/2004 11:00 AM KCC Agent: JIM HOLLAND

Actual Plugging Report:

PUMP 200# HULLS WITH 25 SX CMT. DISPLACE WITH MUD & PRESSURE TO 500 PSIG. SHUT IN. 1ST PLUG PULL OUT OF HOLE TO 1450'. CIRCULATE HOLE WITH MUD & PUMP 50 SX CMT. GOOD CIRCULATION. 2ND PLUG PULL OUT OF HOLE TO 500'. SDON. 02/13/04: CIRCULATE HOLE & PUMP 30 SX CMT AT 500'. GOOD CIRCULATION. 3RD PLUG PULL OUT OF HOLE TO 40'. LOAD HOLE & PUMP 10 SX CMT TO SURFACE.

Perfs:

Top	Bot	Thru	Comments
2175	2190		
2140	2149		

RECEIVED  
FEB 23 2004  
KCC WICHITA

Remarks: USED COMMON CEMENT BY SARGENTS. RECOVERED 1616' OF 5 1/2" CASING.

Plugged through: CSG

District: 01

RECEIVED  
FEB 19 2004  
KCC Dodge City

Signed Jim Holland (TECHNICIAN)  
INVOICED  
DATE 2-24-04  
INV. NO. 2004061207

Form 100