

RECEIVED

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION FEB 23 2004 OIL & GAS CONSERVATION DIVISION WELL PLUGGING RECORD KCC WICHITA K.A.R. 82-3-117

Form CP-4 December 2003 Type or Print on this Form Form must be Signed All blanks must be Filled

Lease Operator: Alan Vonfeldt
Address: 128 Eves Drive, Russell, KS 67665
Phone: (785) 483-6446 Operator License #: 7281
Type of Well: D&A Docket #:
The plugging proposal was approved on: 11-26-03
by: Herb Deines, Hays (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (if needed attach another sheet)
Depth to Top: Bottom: T.D. 3113
Depth to Top: Bottom: T.D.
Depth to Top: Bottom: T.D.

API Number: 15-167-23240-0000
Lease Name: Carter
Well Number: 7
Spot Location (QQQQ): - S/2 - SW - NW
2970 Feet from North / South Section Line
4620 Feet from East / West Section Line
Sec. 33 Twp. 14S S. R. 13 East West
County: Russell
Date Well Completed: 11-26-03
Plugging Commenced: 11-26-03
Plugging Completed: 11-26-03

Show depth and thickness of all water, oil and gas formations.

Table with 7 columns: Oil, Gas or Water Records (Formation, Content) and Casing Record (Surface Conductor & Production) (From, To, Size, Put In, Pulled Out). Row 1: Surface, 0, 625, 8 5/8", 625, None.

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.


Plugged with 140 sacks 60/40 Poz., 6% Gel., 1/4# flocele. 1st. plug - 25 sacks @ 3100', 2nd. plug - 80 sacks @ 625', wiper plug - 10 sacks @ 40' to surface, rathole - 15 sacks, mousehole - 10 sacks.

Name of Plugging Contractor: Allied Cementing Company, Inc. / Vonfeldt + Drilling License #: 9431
Address: P.O. Box 31, Russell, Kansas 67665 PO Box 611 Russell, KS
Name of Party Responsible for Plugging Fees: Alan vonfeldt
State of Kansas County, Russell, ss.

Alan Vonfeldt (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) Alan Vonfeldt
(Address) 128 Eves Drive, Russell, Kansas 67665

SUBSCRIBED and SWORN TO before me this 14th day of February, 2004



Cheryl M. Payne Notary Public My Commission Expires: August 30, 2007

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

RECEIVED
FEB 23 2004
KCC WICHITA

DRILLERS WELL LOG

Date Commenced: November 21, 2003
Date Completed: November 26, 2003

Alan Vonfeldt
Carter #7
S/2 SW NW Sec. 33-14S-13W
Russell County, Kansas

ELEVATION: 1682' G.L.
1687' K.B.

0 - 71' Sand
71 - 284' Quartz
284 - 1645' Sand & Shale
1645 - 2000' Shale
2000 - 2370' Shale & Sand
2370 - 2740' Shale
2740 - 2885' Shale & Lime
2885 - 3113' Shale
3113' R.T.D.

FORMATION DATA

Anhydrite 622'
Grand Haven 2185'
Tarkio Lime 2258'
Elmont 2325'
Topeka 2536'
Heebner 2770'
Toronto 2788'
Lansing 2835'
Base Kansas City 3091'
Arbuckle 3104'
R.T.D. 3113'

Surface Pipe: Set 23#, new, 8 5/8"
casing @ 625' with 300 sacks 60/40
Poz., 3% CC, 2% Gel.

AFFIDAVIT

STATE OF KANSAS)
)
) ss:
COUNTY OF RUSSELL)

Alan Vonfeldt of lawful age, does swear and state that the facts and statements herein are true and correct to the best of his knowledge.

Alan Vonfeldt
Alan Vonfeldt

Subscribed and sworn to before me this 17th day of February, 2004.

My Commission Expires:

August 30, 2007

Cheryl M. Payne
Cheryl M. Payne, Notary Public

