



ROBERT B. DOCKING Governor
DALE E. SAFFELS Chairman
JULES V. DOTY Commissioner
JAMES O. GREENLEAF Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

15-147-20051-00-00

RECEIVED
STATE CORPORATION COMMISSION
NOV 8 1968
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. ~~Elie~~ Ehrlich of Murfin Drlg. has this

date requested permission to plug the following described well:

Mr. Ehrlich guarantees payment of the plugging fee.

Operator's full Name: Cameron K. Reed

Complete Address: 20 West 9th St. Kansas City, Mo.

Lease Name: Lanman Well No. 1

Location: SW SE SW Sec. 21 Twp. 1 Rge. 17 (E)(W) XX

County: Phillips Total Depth 3628 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Ehrlich was instructed to plug the well as follows:

Gun pits, circulate heavy mud, set cementing plug at 1050' and displace
70 sc cement thru drill pipe. Heavy mud to 180' set cement plug and
displace 20 sc cement. Heavy mud to 40' set cementing plug, 1/2 sc hulls
and 10 sc cement to base of cellar. Plug rat hole with 2 sc cement.

Very truly yours,

Leo F. Massey
Conservation Division Agent