

6-14 15-147-19013-00-00

To: 6 010674
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- Old Well
NW, SEC. 3, T. 1 S, R. 18 W/E
_____ feet from S section line
_____ feet from E section line
Lease Name Furse Well # B-1
County Phillips 113-49
Well Total Depth 3492 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet

TECHNICIAN'S PLUGGING REPORT
Operator License # 5646
Operator: Hawn Pet Inc.
Name & Address Box 1065
McPherson, Ks.

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Hawn Pet Inc. License Number _____

Address Same

Company to plug at: Hour: 8:00AM Day: 14 Month: June Year: 19 89

Plugging proposal received from Bob Robertson

(company name) Same (phone) _____

were: Order 400 sks cement 65/35 poz 8% gel 500# hulls. 4 1/2" casing at 3460'
2 3/8" tubing at 3348' Packer at 1516' Elev. 2036' Squeezed at 1310' w/300 sks.
S.L. Dakota 1150 Anhydrite top 1663'
Top 886'

Plugging Proposal Received by D.F.B.
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 3:00Pm Day: 14 Month: June Year: 19 89

ACTUAL PLUGGING REPORT Pulled rods and pump. Pumped down tubing 25 sks cement

displaced to T.D. Shot tubing and casing at 1660' to 1662.5' w/10 shots. Cut tubing
at 1460' and pulled. Pumped down 4 1/2" casing 65 sks cement, then 160 sks cement w/400#

Max pres 1000#. Closed w/400#. Pumped down 8 5/8" 150 sks cement w/100# hulls.
Max pres. 500. Closed w/200#.

STATE CORPORATION COMMISSION

JUN 15 1989

Remarks: Allied Cement Co.
(if additional description is necessary, use BACK of this form.)

CONSERVATION DIVISION
Wichita, Kansas

INVOICED
I will ~~not~~ reserve this plugging.

DATE 6-21-89

INV. NO. 25096

6-14

Ad S.

Signed Dale F. Balthazor
(TECHNICIAN)

Dale F. Balthazor FORM CP-2/3
Rev. 01-84