

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-147-20164-00-00  
Spot: CSWSWSW Sec/Twnshp/Rge: 3-1S-18W  
330 feet from S Section Line, 4950 feet from E Section Line  
Lease/Unit Name: WALKER Well Number: 1A  
County: PHILLIPS Total Vertical Depth: 3436 feet

Operator License No.: 32819  
Op Name: BAIRD OIL COMPANY LLC  
Address: 113 W. MAIN - PO BOX 428  
LOGAN, KS 67646

Conductor Pipe: Size feet:  
Surface Casing: Size 8.625 feet: 214 150 sx cmt  
Production: Size 4.5 feet: 3427 250 sx cmt  
Liner: Size feet:

*8/11.67*

Well Type: OIL UIC Docket No: Date/Time to Plug: 08/29/2001 10:00 AM  
Plug Co. License No.: 32819 Plug Co. Name: BAIRD OIL COMPANY LLC  
Proposal Rcvd. from: JIM R. BAIRD Company: BAIRD OIL COMPANY LLC Phone: (785) 689-7456

Proposed  
Plugging  
Method:

Ordered 9 yards Redi-Mix - 5 sxs common cement - 3000# sand with 42 gallons water per yard.

Plugging Proposal Received By: CARL GOODROW Witness Type: Plugging Operations 100% Witnessed (Complete)  
Date/Time Plugging Completed: 08/29/2001 12:00 PM KCC Agent: CARL GOODROW

Actual Plugging Report:

8 5/8" set at 214' w/150 sxs cwc. 4 1/2" set at 3427' w/250 sxs.  
Prod.Perfs 3238' - 3360'. PBTD 3388'.  
Cut off casing - filled 8 5/8" annulus and 4 1/2" with 9 yards Redi-Mix.  
Plug complete.

RECEIVED  
SEP 11 2001  
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: CSG

District: 04

*JP*

Signed Carl Goodrow  
(TECHNICIAN)

INVOICED

Form CP-2/3

DATE 9-11-01

INV. NO. 2002060450

SEP 05 2001

LELAND BAIRD #1A WALKER 3-1-18W  
 LOGAN, KS. SW SW SW  
 CONTR. ABERCROMBIE DRILLING CTY. PHILLIPS  
 GEOL. BILL IVERSON FIELD HUFFSTUTTER  
 E 1997 RB 8/27/73 CARD ISSUED 2/7/74 IP P 20 BOPD + WTR  
 LANS 3235-87

+	+	+
+	+	+
+	+	+

SMP	TOPS	DEPTH	DATUM
ANH		1618	+ 379
HEEB		3156	-1159
TOR		3184	-1187
LANS		3202	-1205
RTD		3435	-1438

8-5/8" 216, 5 1/2" 3434/150SX  
 NO LOG  
 DST (1) 3221-3245/30-30-30-30, 2' FO, 30'  
 SOCM, BHP 430-394#, FP 18-30#  
 DST (2) 3245-3287/30-30-30-60, 3' FO,  
 15' SOCM, BHP 239-298#, FP 11-35#  
 DST (3) 3287-3300/30-30-30-30, 2'M,  
 ALL PRESS 4#  
 DST (4) 3345-85/30-30-30-60, 5' OCM, +  
 TR OIL, TOP OF TOOL, BHP 143-167#,  
 FP 11-30#  
 (TURNED TO LELAND BAIRD AT 3385')  
 CO & PF (LANS) 3235-87 OA, A 275, POP

INDEPENDENT OIL & GAS SERVICE  
 WICHITA, KANSAS