

4-032420

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Number: 15-147-00401-0000

C NE NE /4 SEC. 04, 01, 18 W
4620 feet from S section line
660 feet from E section line

Fischer

Operator license# 5611

Lease: Fischer Well # 8-1

Operator: Bruce Oil Company

County: Phillips *111.15*

Address: 406 Ponderossa Court
McPherson, Kansas 67460 *6/2*

Well total depth 3420 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 140 feet

Aband. oil well , Gas well , Input well , SWD , D & A

Plugging contractor: Bruce Oil Company License# 5611

Address: 406 Ponderossa Court - McPherson, Kansas 67460

Company to plug at: Hour: P.M. Day: 02 Month: June Year: 2000

Plugging proposal received from: Lonny

Company: Bruce Oil Company Phone: _____

Were: Order 280 sxs 60/40 pozmix - 10% gel - 400# hulls.

RECEIVED
KANSAS CORP COM
2000 JUN 15 P 4: 26

Plugging Proposal Received by: Carl Goodrow

Plugging operations attended by agent? All , Part , None

Completed: Hour: 2:30 P.M., Day: 2 Month: June Year: 2000

Actual plugging report: 8 5/8" set at 140' cwc. 4 1/2" set at 3412' w/N.A. sxs.
Prod Perfs 3193' - 3410'. Critical area control shots at 1900' and 1060'.
Squeezed 4 1/2" with 230 sxs cement blend with 500# hulls mixed in to Max. P.S.I. 600#.
Squeezed 8 5/8" with 50 sxs cement blend to Max. P.S.I. 300#. Plug complete.


Remarks:

Condition of casing(in hole): GOOD _____ BAD _____ Anhy.plug: YES NO _____
Bottom plug(in place): YES _____, CALC _____, NO _____ Dakota plug: YES , NO _____
Plugged through TUBING _____, CASING _____ Elevation: _____ GL

I did / did not observe the plugging.

Carl Goodrow
(agent)

INVOICED 100.
DATE *6/16/00*
INV. NO. *61881*



BUICK DRLG & W P SIMMONS

#1 FISHER

4-1-18W
C NE NE

Contr. BUICK DRLG

PHILLIPS

County

E 1973 RB Comm.

Comp. 8-4-61

IP 50 BOPD/LANS

Tops	Depth	Datum
HFB	3146	-1173
TOR	3175	-1202
LANS	3193	-1220
B/KC	3415	-1432
MARM	3416	-1443
TD	3420	-1447

Casing
 8" 140
 5" 3412
 DST 3212-55/1 HR, 55' OCM, BHP
 1080#
 CO 3374: PERF 4/3345-46: 4/3349-
 50: 4/3325-26: ACID 1000: 3 1/2 BOPH
 /4 HRS: PB 3310: 4/3285-86: 3268-
 69: ACID 1000: 4 BOPH/4 HRS: PB
 3254: 4/3246-47: 4/3231-32: ACID
 1000: 6 BOPH: CO 3374: SWB 8
 FREDRICKSBURG POOL BOPH/4 HRS

+	+	+
+	+	+
+	+	+

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS

RECEIVED
STATE CORPORATION COMMISSION

JUN 6 2000

CONSERVATION DIVISION
Wichita, Kansas