

6 010609

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

4-22-88 15-147-20213-00-00
API NUMBER 15- Old Well

SW NW, SEC. 3, T 1 S, R 18 W/EX
feet from S section line
feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5646

Lease Name Furse Well # B-3

Operator: Hawn Petroleum Inc.
Name & Address: Box 1065
McPherson, Kansas
67460

County Phillips 113.26
Well Total Depth 3485 feet
Conductor Pipe: Size feet
Surface Casing: Size 8 5/8" feet 212

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Hawn Petroleum Inc. License Number 5646

Address Box 1065, McPherson, Kansas 67640

Company to plug at: Hour: 8:30 AM Day: 22 Month: April Year: 19 88

Plugging proposal received from Bob Robertson

(company name) Hawn Pet (phone)

were: Order 350 sks 65/35 Pozmix 10% Gel 2% Econolite and 500# Hulls.

4 1/2" at 3480'.

Elev: 2017' Dakota S.L.D. 1150' Top Dakota 867'

Anhydrite 1641' - 1652'. Perf at 1167' and 1650'.

Plugging Proposal Received by D.F.B.
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: Day: 22 Month: April Year: 19 88

ACTUAL PLUGGING REPORT Pumped down 4 1/2" 50 sks cement. Then, 125 sks cement w/200# Hulls.

Pumped down 8 5/8" 100 sks cement w/300# Hulls. 800# max pressure. Closed w/400#.

Pumped down 4 1/2" 75 sks cement w/100# Hulls. Max pressure 900 closed w/500# Hulls.

RECEIVED
STATE CORPORATION COMMISSION
JUL 6 1988

Remarks: (If additional description is necessary, use BACK of this form.)

I (we) do not desire this plugging.

DATE 7-7-88

Signed Dale F. Balthazor
(TECHNICIAN)

INV. NO. 21220
4-22-88 AUG 3 1988

Dale F. Balthazor
FORM CP-2/3
Rev. 01-84