

15-147-0064700-00

DISTRICT CONSERVATION AGENT'S REPORT

R

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. _____

LOCATION NW NW NE

SEC. 4 TWP. 1 RGE. 18 *W*

Dry Hole Abandoned Oil Well _____ Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. B-1 Lease Fisher

Operator Alpine Oil & Royalty Address Wichita, Kans

Field _____ County Phillips

Total Depth 3468 Feet.

(Describe briefly the manner in which the well was plugged)

8 5/8" at 170' circulated with cement - ~~8x8~~ 5 1/2" at 3468' with
125 sax cement behind - perforations at 3332'.

Filled with chat to 3325', set 4 sax cement with dump bailer,
pulled 2700' 5 1/2", filled hole with mud to 170', set rock bridge and
15 sax cement, mud to 35', set rock and 10 sax cement to bottom
cellar.

PLUGGING
FILE SEC 4 T 1 R 18
BOOK PAGE 9 LINE 26

RECEIVED
STATE CORPORATION COMMISSION
APR 18 1952
CONSERVATION DIVISION
Wichita, Kansas

Edwin Jones
District Conservation Agent
Date 4-15-52

f