

KANSAS

RP

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION
AUG 26 1968
CONSERVATION DIVISION
Wichita, Kansas

15-147-20045-00-00

Operator's Full Name Petroleum Management, Inc.

Complete Address: 1515 Wichita Plaza Wichita, Kansas

Lease Name Lahman Well No. 1

Location NE SW SW Sec. 5 Twp. 1 Rge. 17 (E) (W) X

County Phillips Total Depth 3630'

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D & A X

Other well as hereafter indicated: _____

Plugging Contractor: Red Tiger Drlg.

Address: Wichita, Kansas License No. _____

Operation Completed: Hour 5P Day 23 Month 8 Year 1968

The Above well was plugged as follows:

RTD 3630' 8 5/8 csg set at 200' cwc Cem. Mat. 100 sc 50-50 poz cem. W/6% total gel.
Gunned pits, circulated heavy mud, set cementing plug at 1200' and displaced 70 sc cem.
thru drill pipe. Heavy mud to 210' set cementing plug and displaced 20 sc cement thru
drill pipe. Heavy mud to 40' set cementing plug, 1/2 sc hulls and 10 sc cement to base
of cellar. Plugged rat hole with 2 sc cement.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo F. Massey
Well Plugging Supervisor

DATE 8/26/68
INV. NO. 8353-u