



KANSAS

Form CP-3
Rev. 6-26-62

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION
NOV 8 1968
CONSERVATION DIVISION
Wichita, Kansas

15-147-20051-00-00

Operator's Full Name Cameron K. Reed

Complete Address: 20 west 9th St. Kansas City, Missouri

Lease Name Lanman Well No. 1

Location SW SE SW Sec. 21 Twp. 1 Rge. 17 (E) (W) XX

County Phillips Total Depth 3628

Abandoned Oil Well Gas Well Input Well SWD Well D & A XX

Other well as hereafter indicated:

Plugging Contractor: Murfin Drlg.

Address: Wichita, Kansas License No.

Operation Completed: Hour 9A Day 6 Month 11 Year 1968

The Above well was plugged as follows:

~~RHD~~ 3628' 8 5/8 csg set at 207' cwc Cmt. mat. 50-50 poz cmt W/6% total gel.

Gunned pits, circulated heavy mud, set cementing plug at 1050' and displaced 70 sc cmt.

thru drill pipe, Heavy mud to 180' set cementing plug and displaced 20 sc cement thru

drill pipe, Heavy mud to 40' set cementing plug, 1/2 sc hulls and 10 sc cement to base

of cellar. Plugged rat hole with 2 sc cement.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 11/8/68

INV. NO. 8786-u

Signed: [Signature]
Well Plugging Supervisor