

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission  
Conservation Division  
800 Bitting Building  
Wichita, Kansas

15-147-00074-00-00

FILE NO. \_\_\_\_\_

LOCATION NE SW SE

SEC. 23 TWP. 1 RGE. 17

Dry Hole X Abandoned Oil Well \_\_\_\_\_ Abandoned Gas Well \_\_\_\_\_

I have today completed supervision of plugging of:

Well No. 1 Lease Schluntz

Operator The Bay Pet Corp, Address Wichita, Kans

Field \_\_\_\_\_ County Phillips

Total Depth 3650 Feet.

(Describe briefly the manner in which the well was plugged)

8 5/8" at 214' circulated with cement - 5 1/2" at 3647'

with 150 sax behind. Lane Wells plugs to 3472', top  
perforations at 3456'.

Filled with sand to 3440', set 4 sax cement with dump bailer,  
pulled 1201' 5 1/2", filled hole with mud to 214', set rock  
bridge and 15 sax cement, filled with mud to 35', set rock  
and 10 sax cement to bottom cellar.

RECEIVED  
STATE CORPORATION COMMISSION

JUN 11 1951

CONSERVATION DIVISION  
Wichita, Kansas  
J. J. [Signature]  
District Conservation Agent

PLUGGING  
FILE SEC 23 TWP. 1 RGE. 17  
BOOK PAGE 74 LINE 7

Date 6-5-51